

ITEM	14
MANAGER'S REPORT NO.	10
COUNCIL MEETING	95/03/06

TO: CITY MANAGER **DATE:** 1995 03 01
FROM: DIRECTOR ENGINEERING **FILE:** 10-01-12
SUBJECT: WORK ORDER:
60-21-115, CANADA WAY/GILMORE WATERMAIN REHABILITATION
PURPOSE: To obtain approval of work order #60-21-115.

RECOMMENDATION:

1. THAT the above work order, as more specifically referred to in this report, be approved.

REPORT

60-21-115 Canada Way/Gilmore Watermain Rehabilitation

Charge: 1995 Provisional Capital Budget \$853,000
Mains, Pumping Stations, etc.

Additional Information: Appearing elsewhere on Council's agenda is an item recommending award of Contract #9502, Canada Way/Gilmore Watermain Rehabilitation. The work includes rehabilitation of existing steel watermains on Canada Way, Willingdon to Gilmore and Gilmore, Douglas to Loughheed. The existing 711mm diameter steel main has experienced numerous leaks in the past and should be rehabilitated to prevent further leaks and damage to the road. This contract will utilize a sliplining process that will provide the most efficient construction method and minimize disruption to traffic and reduce the construction period. The sliplining process is another form of no-dig technology that avoids the conventional open-cut excavation approach which would lead to a significant increase of the construction duration for this project. Total estimated cost of this project is \$853,000 including ancillary work by City forces. Sufficient General Revenue funds are available and these expenditures are included in the Water Utility component of the 1995 Provisional Capital Budget.


DIRECTOR ENGINEERING