



Item	02
Meeting	2010 August 30

COUNCIL REPORT

TO: CITY MANAGER 2010 August 25

FROM: DIRECTOR PLANNING AND BUILDING

SUBJECT: REZONING REFERENCE #05-48
Mixed-Use High-rise Residential and Commercial Development
Metrotown Development Plan Sub-Area 1

ADDRESS: 4509/19/39 Kingsway, 5956/68 Willingdon Avenue and 5955/67 Pioneer Avenue
(See attached Sketches #1 and #2)

LEGAL: See Schedule A

FROM: C3 General Commercial district, C4 Service Commercial District and R5 Residential District and P8 Parking District

TO: Amended CD Comprehensive Development District (based on C3 General Commercial District, RM5 Multiple Family Residential District and Metrotown Development Plan as guidelines and in accordance with the development plan entitled "Proposed Mixed Use Development" prepared by Chris Dikeakos Architects Inc.).

APPLICANT: Bosa Properties Inc.
1800 – 4555 Kingsway
Burnaby, BC V5H 4T8
(Attention: David Williams)

PURPOSE: To seek Council authorization to forward this application to a Public Hearing on 2010 September 21.

RECOMMENDATIONS:

1. **THAT** the predecessor Rezoning Bylaw, Amendment ~~Bylaw~~ Bylaw No. 23/10, Bylaw No. 12817, be abandoned contingent upon the granting by Council of Second Reading of the subject Rezoning Bylaw.
2. **THAT** the introduction of a Highway Closure Bylaw be authorized according to the terms outlined in Section 3.12 of this report, contingent upon the granting by Council of Second Reading of the subject Rezoning Bylaw.

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 2

3. **THAT** the sale be approved in principle of City-owned property for inclusion within the subject development site in accordance with the terms outlined in Section 3.12 of this report, and subject to the applicant pursuing the rezoning proposal to completion.
4. **THAT** a Rezoning Bylaw be prepared and advanced to First Reading on 2010 August 30, and to a Public Hearing on 2010 September 21 at 7:00 p.m.
5. **THAT** the following be established as prerequisites to the completion of the rezoning:
 - a) The submission of a suitable plan of development.
 - b) The deposit of sufficient monies including, a 4% Engineering Inspection Fee, to cover the costs of all services necessary to serve the site and the completion of a servicing agreement covering all requisite services. All services are to be designed to City standards and constructed in accordance with the Engineering Design. One of the conditions for the release of occupancy permits will be the completion of all requisite services.
 - c) The installation of all electrical, telephone and cable servicing, and all other wiring underground throughout the development, and to the point of connection to the existing service where sufficient facilities are available to serve the development.
 - d) The submission of an undertaking to remove all existing improvements from the site prior to Final Adoption of the Bylaw, but not prior to Third Reading of the Bylaw. Demolition of any improvements will be permitted after Second Reading of the Rezoning Bylaw has been granted, provided that the applicant acknowledges that such permission does not fetter Council's ability to grant or not to grant Third Reading and/or Final Adoption of the Rezoning Bylaw. In addition, the demolition of any improvements will be permitted at any time if they are vacant and considered by staff to be subject to misuse and vandalism.
 - e) The consolidation of the net project site into one legal parcel.
 - f) The dedication of any rights-of-way deemed requisite.
 - g) The undergrounding of existing overhead wiring abutting the site.
 - h) The granting of any necessary statutory rights-of-way, easements and/or covenants including, but not limited to, those identified in Section 3.7 of this report.

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 3

- i) The provision of a public pedestrian walkway statutory right-of-way from Kingsway to Hazel Street, within the closed portion of Pioneer Avenue, and the construction of a concrete walk and lighting to the approval of the Director Engineering.
- j) Compliance with the guidelines for underground parking for visitors.
- k) Compliance with the Council-adopted sound criteria.
- l) The provision of two covered car wash stalls and adequately sized and appropriately located garbage handling and recycling material holding space and a commitment to implement recycling provisions.
- m) The submission of a suitable on-site stormwater management system to the approval of the Director Engineering, and the granting of a Section 219 covenant and deposit of sufficient monies to guarantee its provision and continuing operation.
- n) The submission of a Site Profile and resolution of any arising requirements.
- o) The pursuance of green building practices for the proposed development in accordance with Section 3.3 of this report.
- p) The determination of an agreement with the Strata Corporation of 4505 Hazel Street regarding the protection and/or replacement of identified trees proximate to the property line on 4505 Hazel Street.
- q) The utilization of an amenity density bonus through the provision of a 6,100 sq.ft. non-profit office space on the third floor, to be transferred to City ownership with the creation of an airspace parcel and protected by a Section 219 Covenant in accordance with Section 3.2 of this report.
- r) The design and provision of units adaptable to persons with disabilities (the provision of special hardware and cabinet work being subject to the sale/lease of the unit to a disabled person) with allocated disabled parking spaces protected by Section 219 Covenant.
- s) Completion of the Highway Closure Bylaw
- t) Completion of the sale of City property.

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 4

- u) The provision of facilities for cyclists including provision of resident bike lockers, commercial bike racks, visitor bike racks and commercial end of trip facilities in accordance with Section 3.17 of this report.
- v) The deposit of the applicable Parkland Acquisition Charge.
- w) The deposit of the applicable GVS & DD Sewerage Charge.
- x) The deposit of the applicable School Site Acquisition Charge.
- y) The deposit of the applicable Metrotown Public Open Space Charge.
- z) The deposit of the applicable Metrotown Grade-separated Pedestrian Linkage Over Kingsway Charge.
- aa) The submission of a written undertaking to distribute area plan notification forms, prepared by the City, with disclosure statements; and, to post area plan notification signs, also prepared by the City, on the development site and in the sales office in prominent and visible locations prior to Third Reading, or at the time marketing for the subject development commences, whichever is first, and remain posted for a period of one year, or until such time that all units are sold, whichever is greater.

REPORT

1.0 REZONING PURPOSE

The purpose of the proposed rezoning bylaw amendment is to permit the development of a mixed-use hotel and apartment tower over a three storey retail podium.

2.0 BACKGROUND

- 2.1 The subject site is located within the Council adopted Metrotown Development Plan area, on the northeast corner of Kingsway and Willingdon Avenue. The subject site is comprised of seven properties including 4509/19/39 Kingsway, 5956/68 Willingdon Avenue and 5955/67 Pioneer Avenue and the Pioneer Avenue and internal lane rights-of-way. The subject site currently consists of a demolished and remediated gas station site, a number of commercial buildings, a single-family dwelling and three lots currently used for surface parking. The existing buildings are boarded and in vacant condition.

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 5

2.2 The subject application went to a Public Hearing on 2008 May 27, and was subsequently given Second Reading on 2008 June 09. The development plan presented at Public Hearing had shown the site to be developed with a single 34-storey mixed use high-rise tower (9 storeys office, 22 storeys residential) over a two storey commercial podium. The proposal also involved a 6,106 sq. ft. non-profit office component (City-owned as a community amenity contribution) on the third floor. It is noted that, upon Council's granting of Second Reading to the subject amendment bylaw, the Metrotown Development Plan was amended to include the RM5 and C3 Districts as use and density guidelines for the subject site. Since that time, the developer has submitted a revised concept that was initially intended to be presented to a Public Hearing on 2010 July 27. The revised concept has now been refined and is suitable for presentation to a forthcoming Public Hearing. The refined development concept consists of:

- a 45 storey single mixed use tower consisting of hotel (formerly office) and residential uses inclusive of a 3 storey commercial/retail podium;
- the addition of a commercial fitness facility on the third floor;
- improved architectural treatment for the building's massing and facade;
- street-front access for the City's non-profit office space from the proposed pedestrian walkway (within the closed Pioneer Avenue right-of-way);
- improved relationship to the street, contributing to an improved pedestrian orientation; and,
- Leadership in Energy and Environmental Design (LEED) standards, rather than Built Green, being used as a measure of building efficiency and green building standards for the project's residential component.

The proposed changes to the development plan for the subject site would maintain this site's strategic commercial value, by providing hotel support for Burnaby's motion picture, high tech, corporate and tourism industries, furthering Metrotown's maturation as a regionally significant commercial area. Furthermore, under the revised concept there continues to be a strong ground oriented retail and restaurant use component for this key corner within Metrotown. Development of this key site within the Town Centre will also result in a signature building that may act as a catalyst for further substantial redevelopment within the area. Therefore, the proposed changes are considered merited and are supported by staff.

2.3 The applicant has now submitted a plan of development suitable for presentation to a Public Hearing.

3.0 GENERAL COMMENTS

3.1 The development proposal is for a single mixed use high-rise tower above a 3-storey retail podium along the Kingsway and Willingdon Avenue frontages, with a City-owned 6,106 sq. ft. non-profit office space and a residential amenity space on the third floor/podium deck. The tower itself is comprised of 26 storeys of residential (202 units)

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 6

13 storeys of hotel (169 rooms), including hotel amenity level. It is noted that of the identified 169 rooms, 143 are configured as long stay-type units, which include full in-suite kitchen and bath facilities. These units are intended to serve the motion picture, high-tech and corporate sectors where accommodation might be required for up to 90 days, although the hotel operator has indicated that typical suite occupancy does not extend beyond two weeks. The development proposes an overall height of 45 storeys, including mechanical levels on floors 18, 44 and 45, with extensive green roofs/decks above the second and third floors. Vehicular access is separated, with hotel/commercial vehicle access via Willingdon Avenue and residential access via the Hazel Street cul-de-sac.

Maximum permitted density for the overall development is governed by the RM5 Multiple Family Residential District (2.2 FAR plus a 0.4 FAR density bonus) for the residential component and the C3 General Commercial District (6.0 FAR) for the commercial component, for a total additive potential density of 8.6 FAR. The applicant is pursuing the maximum residential density of 2.6 FAR and 3.15 FAR of commercial density, for a total maximum FAR of 5.75. The proposed development on this key intersection within the Metrotown Town Centre is being proposed as a signature building with integrated green building practices. The applicant will be required to pursue a Comprehensive Sign Plan for the development. Any potential sky signs will require a further rezoning application.

- 3.2 The requested amenity density bonus of 0.4 F.A.R. provides for an additional 28,180.4 sq.ft. of floor area (subject to confirmation by site survey) with an estimated value provided by the Legal Department of \$2,000,808.40 based on \$71 per sq.ft. buildable. On 2008 April 07, Council adopted the recommendation of the Community Development Committee, that Council approve a non-profit office space as the community benefit to be achieved through the development. The revised development scheme continues to incorporate a non-profit office component as the approved community benefit. The applicant has agreed to provide to the City approximately 6,106 sq.ft. of non-profit office space on the third floor of the podium component as an air space parcel and 13 allocated parking spaces within the underground parking. The non-profit office space will be turn-key ready for occupancy with the exception of office furniture and equipment. The non-profit office space will have its own HVAC system and other services and access to private washrooms. The applicant is required to grant any required easements and/or statutory rights-of-way to provide access from the air space parcel to the ground floor commercial lobby and to the 13 allocated underground parking spaces. The provision of non-profit office space within the Metrotown Town Centre and specifically on this prime corner is an asset to the City and to non-profit office users as it is within the core commercial office component of the plan, has access to a broad range of community services and amenities and is within 500m of the Metrotown SkyTrain station and bus loop.

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 7

- 3.3 The developer is incorporating green building practices for the proposed development insofar that they will be pursuing Leadership in Energy and Environmental Design (LEED) Silver equivalency for the overall development.
- 3.4 As an additional component of the green building sustainability approach, and reflective of the location of this development within Metrotown and proximity to public transit, the applicant is proposing a Transportation Demand Management (TDM) initiative involving the development's active participation and support for car-sharing in the neighbourhood. The Co-operative Auto Network (CAN) is a not-for-profit co-operative incorporated to foster car sharing as an environmentally responsible transportation option resulting in fewer cars in the community. The developer has proposed to provide funding for the one time registration/lifetime membership fee with CAN for the 202 residential units, donate 3 cars (including 1 hybrid) to CAN and allocate three surface parking spaces for their dedicated parking. Members pay a small monthly administration fee to cover some of the fixed costs to the car, and when they use a car, they pay low fees for use by the hour or by kilometer. The cars will be located within the residential entry turn-a-round and available for the all residential owners/tenants, and by all CAN members, thus facilitating sustainable transportation for residents of the surrounding neighbourhood. Staff is supportive of a maximum residential parking reduction of 0.1 spaces (from 1.6 spaces/unit to 1.5 spaces/unit) for the development resulting in a reduction of 20 residential tenant spaces in exchange for the provision and continued operation of car co-op spaces. The reduction of parking will be within the residential underground component and will not affect the 0.25 spaces / unit allocated for visitors. The provision and retention of car co-op spaces and vehicles on the site will be secured in perpetuity by way of 219 Covenant, right-of-way and/or easement agreements which would allow the City to assign the use of the car co-op spaces in whole or in part to an alternate co-op should CAN cease to operate or choose to use fewer than the three spaces for its car co-op program.
- 3.5 The applicant has elected to provide 10 adaptable units (5% of unit total) and has provided 10 resident and 1 visitor handicap parking stalls within the underground parking structure. Handicapped parking stalls will be protected by Section 219 Covenant as common property to be administered by the Strata Corporation.
- 3.6 The Director Engineering will be requested to prepare an estimate for all services necessary to serve this site. The servicing requirements will include, but not necessarily be limited to:
- The provision of a right turn lane on Kingsway abutting the subject site and provision of separated sidewalks with stamped concrete boulevards, street trees, street lighting and pedestrian lighting across the development frontage. The applicant will upgrade and relocate the traffic signals and trolley line poles as required.
 - The provision of access/egress to the hotel/commercial component of the site and for the completion of the Grange St. right turn lane on Willingdon Avenue abutting the

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 8

site including the provision of separated sidewalks with stamped concrete boulevards, street trees, street lighting and pedestrian lighting across the development frontage.

- Pioneer Avenue will be closed to vehicles and consolidated with the development site, for the purpose of creating an 8.0m wide public pedestrian pathway linking Kingsway and Hazel Street. Emergency vehicle access for the development site is not required via the Pioneer right-of-way. The public pedestrian pathway will enable convenient resident access to Kingsway through an engaging, a well lit, landscaped corridor constructed with a minimum 2.0m concrete walkway with special paving design, pedestrian lighting, street trees, planters, benches and public art.
- Hazel Street cul-de-sac is to be upgraded to its final standard.

Required road dedications are 3.72m (12.2 ft.) widening on the Kingsway frontage, 5.79m (19.0 ft.) widening on the Willingdon Avenue frontage, and a 11m² dedication for the completion of the Hazel Avenue cul-de-sac.

3.7 Any necessary easements, 219 Covenants and statutory rights-of-way for the site are to be provided, including, but not necessarily limited to:

- Covenant restricting enclosure of balconies;
- Covenant restricting length of stay for hotel guest rooms (30 days for regular rooms and 90 days for long stay rooms);
- Covenant to guarantee the provision and continuing operation of stormwater management facilities;
- Covenant for the provision, retention and maintenance of Public Art within the Pioneer Avenue pedestrian walkway;
- Covenant indicating that project driveway access will not be restricted by gates;
- Covenant to ensure the continued maintenance by the commercial component of the landscaped roof decks above the commercial podium, and landscaped street frontages and public pedestrian walkway;
- Covenant for future air space parcels covering both the commercial and residential components to ensure that the density of development of air space parcels and strata lots comply with the approved CD zoning for the site and to ensure that the overall site continues to function as a single, integrated development;
- Covenant for the provision of 3 car co-op spaces at grade for the location of car co-op cars only;
- Covenant for cycling end-of-trip facilities and bike storage for office/retail employees;
- Covenant ensuring that exhaust fans, venting systems or other mechanical equipment are provided only on approved roof deck areas with sound attenuation;
- Covenant ensuring the provision of 10 resident and 1 visitor handicap accessible parking stalls in the resident parking area for the sole use of the 10

To: City Manager
From: Director Planning & Building
Re: REZONING REFERENCE #05-48
High-Rise Residential and Commercial Development
2010 August 25Page 9

- accessible units and that these stalls, as well as any other handicap accessible parking provided in the residential component of the underground parking, be held in common property to be administered by the Strata Corporation;
- An 8.0m (26.25 ft.) wide statutory right-of-way for pedestrian purposes on the closed portion of Pioneer Avenue;
 - Provision of any statutory rights-of-way and/or access easements for pedestrian purposes, access to parking areas, servicing and circulation; and,
 - Other legal provisions and documentation as required.
- 3.8 In light of the proximity to Kingsway, a noise study is required to ensure compliance with the Council-adopted sound criteria.
- 3.9 Two car wash stalls and an appropriately screened garbage handling and recycling holding area will be provided on site.
- 3.10 The developer is responsible for the undergrounding of the overhead wiring within the subject site and abutting the site along the east side of Willingdon Avenue.
- 3.11 Development Cost Charges:
- a) Parkland Acquisition Charge of \$3.55 per sq.ft. of residential gross floor area
 - b) School Site Acquisition Charge of \$600.00 per unit
 - c) GVS&DD Sewerage Charge of \$590.00 per apartment unit and \$0.443 per sq.ft. of commercial floor area.
 - d) Metrotown Grade-Separated Pedestrian Linkage charge of \$0.306 per sq.ft. of commercial floor area.
 - e) Metrotown Public Open Space charge of \$0.50 per sq.ft. of commercial floor area.
- 3.12 The consolidation of the proposed development site includes the closure of two internal lanes and the Pioneer Avenue road right-of-way between Kingsway and Hazel Street measuring approximately 1,351.7m² (14,550 sq.ft.) which will be achieved through a Highway Closure Bylaw (see attached Sketch #1). The developer will receive credit for the necessary road widening dedications required from the site which measures approximately 638.6m² (6,874 sq.ft.). The net road right-of-way area to be purchased by the applicant is approximately 713.1 m² (7,676 sq.ft.). The Legal Department has established a value of \$203.94 sq.ft. for the City land for a total value of approximately \$1,565,443.40. The value is subject to review by the Legal Department nine months from the date of Second Reading. The internal laneways will be incorporated within the development area; however, an 8.0m portion of the Pioneer Avenue right-of-way will remain open as a landscaped public pedestrian walkway connecting Kingsway to Hazel Street to be maintained by the owner of the commercial component.
- 3.13 An on-site sediment control system is a requirement of Preliminary Plan Approval and must be approved by the Environmental Services Division - Engineering Department.

To: City Manager
 From: Director Planning & Building
 Re: REZONING REFERENCE #05-48
 High-Rise Residential and Commercial Development
 2010 August 25Page 10

- 3.14 A suitable on-site stormwater management system is required to the approval of the Director Engineering. A Section 219 Covenant will be required to guarantee its provision and continuing operation will also be required.
- 3.15 There are no existing trees on site suitable for retention. There are a number of significant trees along the south property line of 4505 Hazel Street adjacent to the development site, two of which may be affected by the subject site's excavation. The applicant has executed an agreement with the Strata Corporation of 4505 Hazel Street on 2010 January 28 to remove the two affected trees and replace them with four specimen coniferous trees along the common property line.
- 3.16 Due to the previous commercial use of the site, a site profile and resolution of any resultant conditions is required.
- 3.17 Bicycle storage space and surface parking racks are to be provided for the residential and commercial tenants and visitors and customers. End-of-trip facilities for the commercial uses are to be provided.

4.0 DEVELOPMENT PROPOSAL

4.1 Site Area

Gross Site:	-	7,183.5 m ² (77,325 sq.ft.)
Dedications:	-	638.6 m ² (6,874 sq.ft.)
Net Site	-	6,544.9 m ² (70,451 sq.ft.) (Subject to detailed survey)

4.2 Density

F.A.R. Permitted & Provided:		
Residential	-	2.60 F.A.R. (inclusive of 0.40 FAR amenity bonus)
Commercial	-	3.15 FAR
COMBINED TOTAL	-	5.75 FAR

Gross Floor Area Permitted & Provided		
Residential	-	17,016.8 m ² (183,173 sq.ft.) (inclusive of 28,180.4 sq. ft. amenity bonus)
Hotel	-	11,721.5 m ² (126,173 sq.ft.)
Retail	-	5,587.8 m ² (60,149 sq.ft.)
Restaurant	-	730.0 m ² (7,858 sq.ft.)
Fitness Facility	-	2,603.5 m ² (28,025 sq.ft.)
Community Amenity Space	-	567.3 m ² (6,106 sq.ft.)
TOTAL	-	38,226.9 m² (411,484 sq.ft) (excludes 3,000 sq.ft. of residential amenity)

To: City Manager
 From: Director Planning & Building
 Re: REZONING REFERENCE #05-48
 High-Rise Residential and Commercial Development
 2010 August 25Page 11

Site Coverage - 67.42%

- 4.3 Height (all above grade)
- 1 storey restaurant/lobby/retail
 - 1 storey retail
 - 1 storey fitness facility, amenity and non-profit office
 - 13 storey hotel
 - 26 storey residential
 - 3 storey mechanical
-
- 45 Storeys Total**

4.4 Residential Unit Mix

<u>Unit Type</u>	<u>Unit Size</u>
20 studio units :	- 35.6 m ² (383 sq.ft.)
61 one-bedroom units :	- 49.5 – 57.7 m ² (533 – 621 sq.ft.)
106 two-bedroom units:	- 69.0 – 103.6 m ² (743 – 1,115 sq.ft.)
4 two-bedroom + den :	- 123.8 m ² (1,333 sq.ft.)
6 three-bedroom units :	- 116.6 – 159.9 m ² (1,255 – 1,721 sq.ft.)
<u>5 three-bedroom + den units:</u>	<u>- 166.7 m² (1,794 sq.ft.)</u>

TOTAL: 202 UNITS


*Includes 5% (10) adaptable units with (10) allocated resident disabled parking spaces and (1) visitor space.

4.5 Parking

Vehicle Parking	Required	Provided
202 Apartment Units (1.5 spaces/unit)	- 303 (inclusive of 51 visitor spaces)	312
169 Room Hotel (1 space/2 Rooms)	- 85	86
59,704 sq. ft. Retail (1 space/495.16 sq. ft.)	- 121	121
28,025 sq.ft. Fitness Facility (1 space/495.16 sq.ft)	- 57	57
6,106 sq. ft. Non-Profit Office Space (1 space/495.16 sq. ft.)	- 13	13
275 Restaurant Seats (1 space/5 seats)	- 55	55
TOTAL SPACES	- 634	644

To: City Manager
 From: Director Planning & Building
 Re: REZONING REFERENCE #05-48
 High-Rise Residential and Commercial Development
 2010 August 25Page 12

<u>Car Wash Stalls</u>	-	3	3
Bicycle Parking		Required	Provided
<u>Residential</u>			
Secured Residential Lockers (1 locker/unit)	-	202	202
Visitor Rack Spaces (0.2 spaces/unit)	-	40	40
<u>Commercial & Visitor</u>			
Rack Spaces (10% of required parking)	-	33	33
End Of Trip Facilities	-	Bike lockers, showers, lockers, change rooms, water closets and wash basins provided.	
4.6 <u>Communal Facilities</u>	-	Major central garden/green space, swimming pool and internal amenity spaces, landscaped roof decks, memberships in Co-operative Auto Network and access to on-site vehicles.	




 B. Luksun
 Director Planning and Building

EK:JBS/gk
 Attachments

cc: Director Engineering
 City Clerk
 City Solicitor
 Director of Parks, Recreation and Cultural Facilities

**Rezoning Reference #05-48
Schedule "A"**

4509 Kingsway	Parcel A (Reference Plan 17013) of Lot 11 and 12 except: part dedicated road on Plan 76857, DL 153, Group 1, NWD Plan 1316
4519 Kingsway	Westerly half Lot 13 except: part shown on plan with Expropriation Bylaw 30078; Blk 4, DL 153, Grp 1, having a frontage of 33 feet on Westminster Road by full depth as said lot and adjoining Lot 12, NWD Plan 1316
4519 Kingsway	Easterly half Lot 12 except: part shown on plan with Expropriation Bylaw 30078, Blk 4, DL 153, Grp 1, having a frontage of 33 feet on Westminster Road by a full depth of said lot and adjoining Lot 13, NWD Plan 1316
4539 Kingsway	Lot 14 except: part on plan with Bylaw filed 30078, DL 153, Grp 1, NWD Plan 1316
4539 Kingsway	Parcel 'A' (J56134E), Lot 13, DL 153, Grp 1, NWD Plan 1316
5956 Willingdon Ave	Lot 9, DL 153, Grp 1, NWD Plan 1316
5968 Willingdon Ave	Lot 10, DL 153, Grp 1, NWD Plan 1316
5955 Pioneer Ave	Lot 16, DL 153, Grp 1, NWD Plan 1316
5967 Pioneer Ave	Lot A, DL 153, Grp 1, NWD Plan LMP22502



Planning and Building Department


Scale: 1 = 2500

Drawn By:

Date: June 2010

REZONING REFERENCE # 05 -- 48
 Kingsway ,Willingdon,Pioneer

Sketch # 1



Metrotown

City of Burnaby

Composite Sketch of Development Guidelines

LEGEND:

- 1 > CD (RM1)
- 2 > CD (RM2)
- 3 > CD (RM3)
- 4 > CD (RM4)*
- 5 > CD (RM5)*
- 6 > CD (RM6 / C3)*
- 7 > CD (C3 use guideline)*
- 8 > CD (RM3 / C1)*
- 9 > CD (RM3 / C2)*
- 10 > Civic Facilities*
- 11 > Public Assembly Precinct*
- 12 > CD (RM3 / Institutional)
- 13 > RM2
- 14 > RM3
- 15 > RM4
- 16 > R8



*Particular Clarification of Guidelines is Required with Planners for any serious development inquiries utilizing those Designated Guidelines.

▣ > Projects identified by a "Square" are Retained but as yet Unconstructed.

▨ > Completed in accordance with Development Guidelines



Planning and Building Department

Scale: N.T.S.

Drawn By:

Date: June 2010

REZONING REFERENCE # 05 -- 48
Kingsway ,Willingdon,Pioneer

Sketch # 2